

Master Work Order

Circle	BAL-ANG-UASL-AP-Telangana		
GIS Code	BA1		
MWO creation Date	04-Jul-2024		
CWIP Locator Code	20236.1739.66783913.CWIP-CL		
M6 Code	HYD/BA1/901		
MWO Home Pass	0		
ROW Cost	0		
Service Cost	139380		

NFA NUMBER	Business/3827/166699	Case ID	BAL-ANG-UASL-AP- Telangana/HYDERABAD/15995	
City	HYDERABAD	Area Name Hyderabad FTTH Network Resilience H34 1QL ATP 2' H27 FY 25 Lot 5		
MWO Number	BAL-ANG-UASL-AP-Telangana/HYDERABAD/Capex/FTTH/B2C/New Rollout/Mix/OSP_OH/04072024/89654			
MWO Start Date	04-Jul-2024	MWO End Date	02-Sep-2024	
Category	New Rollout	Type of Building/area	Mix	
Route Length	1700 mt	ROW Length	0 mt	
Material Cost	76446	ODN Cost	0	
OLT Cost	1116000	Total WO Cost	220007.4	

Service Item						
S.No.	Service description	Service Code	UOM	Service Qty	Service Rate	Service Cost
1	Core Site Installation Service,Type:Site Installation,Scope:Per Site,Details:Fiber rollout: Sign writing on Network element	BOSSCIBG9	Each	33	60	1980
2	Core Site Installation Service,Type:Site Installation,Scope:Per Site,Details:Fixed Mobilization amount - OH Fiber rollout	B0SSCIBX2	Each	1	15000	15000
3	FTTH? Structured overhead rollout	TNL004057	Meter	1700	72	122400
Total Service Cost					139380	

Supply Item						
S.No.	Service description	Service Code	UOM	Material Qty	Material Rate	Material Cost
1	FMS 48F,Rack Mount,3U,with SCAPC Connector&Pigtail	FDM000004	Number	1	3708	3708
2	OFC 48F MLT UNIVERSAL CABLE	OFC000077	Kilometer	1.7	29660	50422
3	Optical Fiber Joint Closure, 48F, Branch Joint	JCL000006	Number	1	880	880
4	Anchoring Clamp - for 10 - 14 mm Cable dia-PA 120 FO 400	TNL004213	Number	54	149	8046
5	Universal Pole Bracket - Single run (for Anchoring /Tensioning)- CASHT	TNL004221	Number	29	84	2436
6	Suspension Clamp - for 8 - 20mm Cable dia- PSR 8 - 20 ADSS	TNL004220	Number	27	80	2160
7	Adjustable Cable Storage Bracket- MALICOIL - M	TNL004212	Number	9	575	5175
8	FTTH Accessories - SS Strap IF - 207	TNL004235	Number	112	27	3024
9	Buckle -CHA 20	TNL004217	Number	85	7	595
Total Material Cost					76446	

Approver Level	Approver	Status	Approver Name	Date
L1	PLANNING_HEAD	L1_Approved	Srinivas M	04- Jul- 2024
L2	PLANNING_TEAM_ADMIN			
L3	SCM_TEAM_MEMBER	SCM_Approved	V V Satyanarayana N	15- Jul- 2024